

数量總括表 市道末寺8号線道路改良工事（2工区）

市道末寺8号線道路改良工事（2工区）

[illegible]

土工集計表

| 測 点 | B : 盛土 (B<2.5m) | | | | | 掘削 (E) | | | |
|------------|-----------------|---------|---------|---------|---------|---------|---------|---------|---------|
| | 距離 (m) | 平積 (m2) | 平均 (m2) | 立積 (m3) | 累積 (m3) | 平積 (m2) | 平均 (m2) | 立積 (m3) | 累積 (m3) |
| | | | | | | | | | |
| NO. 0. 0 | 0. 0 | 0. 82 | | | | 0. 50 | | | |
| NO. 2+5. 3 | 45. 3 | 0. 82 | 0. 82 | 37. 15 | 37. 15 | 0. 50 | 0. 50 | 22. 65 | 22. 65 |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 合計 | | | | | 37. 15 | | | | 22. 65 |

法面工集計

| 名称・仕様 | 面積・延長 | 数量 | 単位 | 適用 |
|---------------------------------------------|----------------|------|----|----|
| 法面整形 盛土部 | A = 2.0 × 45.3 | 90.6 | m2 | |
| 張りコンクリート (t=5cm 18-8-25 W/C ≤ 60%) 法面 | A = 2.0 × 45.3 | 90.6 | m2 | |
| 計 | | 90.6 | m2 | |

舗装工集計

| 名称・仕様 | 面積・延長 | 数量 | 単位 | 適用 |
|--------------------------|-----------------|------|----|----|
| 表層 (t=5cm 密粒度アスコン20F) | | | | |
| 車道部 | A = 0.85 × 45.3 | 38.5 | m2 | |
| 計 | | 38.5 | m2 | |
| 上層路盤 (t=10cm 粒調碎石 M-30) | | | | |
| 車道部 | A = 0.90 × 45.3 | 40.8 | m2 | |
| 計 | | 40.8 | m2 | |
| 下層路盤 (t=20cm 再生碎石 RC-40) | | | | |
| 車道部 | A = 1.00 × 45.3 | 45.3 | m2 | |
| 計 | | 45.3 | m2 | |